



www.LaRosaBuildingGroup.com

Bridgewater Renovation Estimate 1-16-2019

Notes and Clarifications

- Residential prevailing wages are included
- Hazardous materials are an allowance in the estimate
- Building shoring is an allowance in the estimate
- Pricing is based on current market pricing
- Sitework is limited to excavating for the new building
- No wood restoration is included at this time
- Siding is limited to the addition and minor work on the existing structure
- Interior doors are to be pre-hung hollow core units
- Wood flooring is to be retained and sanded. Any new wood flooring will be charged on a per board bases
- Plumbing pricing assumes all distribution piping will be retained and reused in the existing structure



Group	Phase	Description	Takeoff Quantity	Grand Total Amount	
1000.000		GENERAL REQUIREMENTS			
	1061.100	Preconstruction			
		Pre-Construction	175.00 hrs	17,259	
		Preconstruction		17,259	
	1300.010	Personnel: Supervision		, , , ,	
		Project Manager - 3 MO	519.00 hrs	57,328	
		Superintendent - 5 MO	865.00 hrs	76,210	
		Document Control - 2 MO	346.00 hrs	25,024	
		Personnel: Supervision		158,562	
	1510.010	Utilities: Temporary			
		Temp Electricity	5.00 mo	5,917	
		Temp Heat	2.00 mo	13,150	
		Utilities: Temporary		19,067	
	1520.010	Temp: Facilities			
		Storage Trailer	5.00 mo	657	
		Office Trailer	5.00 mo	4,274	
		Temp: Facilities		4,931	
	1520.020	Temp: Supplies			
		Office Supplies	5.00 mo	7,890	
		Temp: Supplies			
	1520.030	Temp: Office Supplies		1,000	
	10201000	Job Sign	1.00 ea	2 104	
		Temp: Office Supplies			
	1530.030	Construction Facilities		2,104	
	1330.030	Sanitary Facilities - 3	5.00 mo	2 367	
		Dumpster - 30 YD Container Flat Fee Single Stream	15.00 EA	mo 7,890 7,890 ea 2,104 2,104 mo 2,367 EA 12,827 15,188 Iff 2,860 mh 3,419	
		Construction Facilities	10.00 27		
	1560.100	Temp: Protection		10,100	
	1300.100	Temp. Fence-6' high w/ 2 gates - 12 Month	500.00 lft	2 860	
		Temp: Protection	300.00 III		
	1580.010	Cleaning		2,000	
	1500.010	Progress Cleaning	40.00 mh	2.410	
		Final Cleaning	3,500.00 sft		
		Cleaning	3,300.00 Sit	5,720	
	1725.040	Close Out Submittals		3,720	
	1725.040	Punch List	8.00 day	8,942	
		Close Out Submittals	8.00 day	8,942	
		GENERAL REQUIREMENTS	5.00 MO	242,524	
1730.000		DEMOLITION			
	1730.100	Demo: Subcontractors			
		Building shoring allowance	Is	65,749	
		Environmental allowance	ls	65,749	
		Demo: Subcontractors		131,499	
	1731.010	Demo: General			
		Interior Demolition	2,800.00 SF	24,590	
		Demo: General		24,590	
	1733.010	Demo: Concrete			
		Remove foundation	32.00 hrs	25,090	
		Demo: Concrete		25,090	
		DEMOLITION		181,179	
				101,179	
2000.000		SITEWORK			
	2315.020	Earthwk: Cut & Fill Etc			
		Excavate and prep for new foundation	136.00 cy	53,257	

Group	Phase	Description	Takeoff Quantity	Grand Total Amount	
	2315.020	Earthwk: Cut & Fill Etc			
		Misc signage and concrete work	1.00 ls	5,260	
		Earthwk: Cut & Fill Etc		58,517	
	2900.010	Landscape: General			
		Seeding	sft	3,287	
		Landscape: General		3,287	
		SITEWORK		61,804	
3000.000		CONCRETE			
	3310.140	Conc: Footings/Walls			
		Footings	15.00 cy	16,273	
		Conc: Footings/Walls		16,273	
	3310.160	Conc: Walls			
		Walls	22.00 cy	23,867	
		Conc: Walls		23,867	
	3310.200	Conc: Piers			
		Piers	1.00 cy	1,060	
		3 new stoop	20.00 cy	15,898	
	0040.010	Conc: Piers		16,958	
	3310.210	Conc: Slabs On Grade	20.00	04.707	
		Slab New Walk	26.00 cy 5.00 cy	24,787 5,424	
		Conc: Slabs On Grade	3.00 cy	30,212	
		CONCRETE		87,310	
4000.000		MASONRY			
	4000.010	Division 4 Subcontractors			
		Stone Assembly on Foundation wall	450.00 sf	20,711	
		Division 4 Subcontractors		20,711	
		MASONRY		20,711	
5000.000		METALS			
	5121.010	Structural: W Shapes			
		HSS 5x5x5/16	2.00 tons	17,095	
		W12x35	2.80 tons	16,569	
		Structural: W Shapes		33,664	
		METALS		33,664	
6000.000		WOOD & PLASTICS			
	6000.010	Division 6 Subcontractors			
		Frame new Cupola	1.00 ls	15,780	
		Division 6 Subcontractors		15,780	
	6111.010	Framing: Floor Joist			
		2x8 Floor Joists sistering 1st and second	2,000.00 If	19,747	
		2x8 Addition joists	1,100.00 If	10,861	
		Roof joists	300.00 If	3,783	
		Framing: Floor Joist		34,391	
	6112.010	Framing: Studs 2x4 > 2x8			
		New 2x4 Wall Framing	210.00 LF	7,564	
		New 2x6 Wall Framing	450.00 lf	17,746	
	6462.040	Framing: Studs 2x4 > 2x8		25,310	
	6162.010	Plywood: Wall Sheathing	4 600 00 of	24.240	
		Wall Sheathing floor Sheathing	4,600.00 sf 650.00 sf	24,249 2,693	
		Plywood: Wall Sheathing	030.00 Si	26,942	
	6163.010	Plywood: Roof Sheathing		20,342	
	0100.010	i iywood. Nooi oficatiiiig			

Group	Phase	Description	Takeoff Quantity	Grand Total Amount
	6163.010	Plywood: Roof Sheathing		
		Roof Sheathing	300.00 sf	2,753
		Plywood: Roof Sheathing		2,753
	6200.010	Finish Carpentry		
		1x4 interior window trim	520.00 If	4,513
		1x4 interior door trim	575.00 If	4,990
		1x4 interior Base trim	790.00 lf	7,376
		1x4 chair rail 1st floor	320.00 lf	2,777
		Wainscoting 1st floor	1,200.00 sf 50.00 lf	8,942
		NEw Exteior railings Finish Carpentry	50.00 11	4,142 32,741
	6410.010	Interior Arch Woodwork		32,741
	6410.010	New Wood Stair	1.00.00	5.917
		Interior Arch Woodwork	1.00 ea	5,917
		WOOD & PLASTICS		143,834
7000.000		THERMAL & MOISTURE PROT		
	7210.010	Insulation: Batt		
		Building Insulation	3,450.00 sf	14,744
		Insulation: Batt		14,744
	7310.010	Shingles: Several Types		
		Roof Shingles	15.00 sq	12,910
		Shingles: Several Types		12,910
	7460.010	Siding: Wd,Vinyl & Fiber		
		Allowance for new work at existing siding	sf	9,862
		NEw Cedar Siding	1,100.00 sf	14,178
		New exterior trim at addition	700.00 If	5,118
		NEw Pedamant Panels	50.00 sf	942
		New Coupola Panels	350.00 sf	4,382
		Siding: Wd,Vinyl & Fiber		34,482
	7710.010	Sheetmetal: Guttr DwnSpt		
		Gutters and Downs	300.00 If	5,128
		Sheetmetal: Guttr DwnSpt		5,128
		THERMAL & MOISTURE PROT		67,264
8000.000		DOORS & WINDOWS		
	8210.010	Doors: Wood		
	02101010	New Inteiror Pre-hung wood door	14.00 ea	9,297
		New Exteior Door	1.00 ea	1,354
		New heardware at restored doors	3.00 ea	2,314
		Doors: Wood		12,966
	8310.010	Doors: Access/Fire		
		Bilco Hatchway	1.00 ea	4,602
		Doors: Access/Fire		4,602
	8550.010	Windows: Wood & Plastic		
		Windows	32.00 ea	27,843
		Windows: Wood & Plastic		27,843
		DOORS & WINDOWS		45,411
9000.000		FINISHES		,
3000.000	0440.040			
	9110.010	GWB Ext Frame: Labor	40.000.00	00.450
		Gypsum Board Walls	10,000.00 SF	39,450
		Gypsum Board Ceilings GWB Ext Frame: Labor	3,400.00 SF	10,954
	0240 040			50,403
	9310.010	Tile: Ceramic	000.00 -£	0.045
		Floor Tile with underlayment	330.00 sf	8,245

Group	Phase	Description	Takeoff Quantity	Grand Total Amount	
		Tile: Ceramic		8,245	
	9640.010	Flooring Wood			
		New Wood Flooring	630.00 sf	7,456	
		Sand and refinish flooring	2,100.00 sf	13,807	
		Flooring Wood		21,263	
	9900.010	Paints & Coatings			
		Paint Gypsum Board	13,400.00 sf	23,788	
		Restore doors	3.00 ea	2,805	
		Paints & Coatings		26,593	
		FINISHES		106,505	
10000.00 0		SPECIALTIES			
	10800.010	Misc Toilet/Bath Equip			
		Toilet & Bath Accessories	4.00 ea	1,578	
		Misc Toilet/Bath Equip		1,578	
		SPECIALTIES		1,578	
11000.00		EQUIPMENT		,,,,,	
0		EQUIT WENT			
	11450.010	Kitchen Appliances			
		Range	1.00 ea	1,512	
		Refrigerator	1.00 ea	2,696	
		Dishwasher Built-In	1.00 ea	868	
		Microwave	1.00 ea	460	
		Kitchen Appliances		5,536	
		EQUIPMENT		5,536	
12000.00 0		FURNISHINGS			
	12300.010	Casework			
	12000.010	Kitchen Cabinets and Counter	1.00 ea	7,232	
		Casework	1.00 00	7,232	
	12490.010			1,202	
	12-100:010	Window Treatment	32.00 ea	3,156	
		Window Treatments	32.00 34	3,156	
		FURNISHINGS		10,388	
45000.00				10,000	
15000.00		MECHANICAL			
0					
	15400.000	Plumbing			
		Plumbing Fixture	9.00 ea	23,670	
		Water Heater	1.00 ea	7,232	
		Plumbing		30,902	
	15700.000	HVAC Systems			
		HVAC Systems	3,500.00 sf	110,459	
		HVAC Systems		110,459	
		MECHANICAL		141,361	
16000.00		ELECTRICAL			
0	40000				
	16000.010	Electrical Complete			
		Electrical	3,500.00 sf	78,242	
		Electrical Complete		78,242	

Group	Phase	Description	Takeoff Quantity	Grand Total Amount
		ELECTRICAL		78,242

Estimate Totals

Description	Amount	Totals	Hours	Rate	Cost Basis	Cost per Unit	
Total		1.227.310					